



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-185-01399-0000

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1964

CONSERVATION DIVISION
Wichita, Kansas

3-23-64

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Orr of Thunderbird Drilling Co. has this
date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Co.

Complete Address: 706 Union Center, Wichita, Kansas

Lease Name: Soden Well No. # 1

Location: SE NE SE Sec. 23 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3930 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Orr was instructed to plug the well as follows:

265' of 8 5/8" surface pipe, cemented with 250 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent