



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-185-19437-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1964
12-7-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Gerd Steincamp of M. S. T. Drilling Co. Inc. has this date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Muir Thompson Inc.

Complete Address: 201 Garlinghouse Bldg., Topeka, Kansas

Lease Name: Lutz "B" Well No. # 1

Location: NE SW NE Sec. 27 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3950 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

287' of 8 5/8" surface pipe, cement circulated with 170 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving