



JOHN ANDERSON, Jr. Governor  
WILLIAM L MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-185-30064-0000

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1965  
5-24-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Neal of Northeastern Petroleum has this date requested permission to plug the following described well:

Mr. Neal guarantees payment of the plugging fee.

Operator's full Name: Northeastern Petroleum Company

Complete Address: 2400 N. Main St., Hutchinson, Kansas

Lease Name: Davidson Well No. # 1

Location: C S/2 SW SW Sec. 27 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3935' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Neal was instructed to plug the well as follows:

273' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Bottom joint of surface pipe had shook loose, and went down hole.

Fill hole with drilling mud to 235', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to the base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent