



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1964
6-3-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Howard Ward of Tommy Ward Drilling Co. has this
date requested permission to plug the following described well:

Mr. Ward guarantees payment of the plugging fee.

Operator's full Name: Woody's Quality Oil Company

Complete Address: 1119 Cravens Bldg., Oklahoma City, Oklahoma

Lease Name: Soeken Well No. # 5

Location: N/2 SW NE Sec. 15 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3840 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ward was instructed to plug the well as follows:

298' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud to 280', 1st cementing plug, bridge with
hulls and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge rat and mouse hole,
and cement with 4 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent