


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Luting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 7 Twp. 27 Rge. 12 (E) W. (W)
Location as "NE/CNW/SW" or footage from lines NW SE NE
Lease Owner Cities Service Oil Company
Lease Name Deistler Well No. 2
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed November 9, 19 50
Application for plugging filed Sept. 25, 19 56
Application for plugging approved Sept. 26, 19 56
Plugging commenced October 22, 19 56
Plugging completed October 26, 19 56
Reason for abandonment of well or producing formation Depleted formation.

If a producing well is abandoned, date of last production October 1, 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Simpson Depth to top 4239 Bottom 4290 Total Depth of Well 4290 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	404'	None
				5-1/2"	4237'	2229'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4290-4225', river sand.
4225-4185', 5 sacks cement.
4185- 300', mud (circulated to surface).
300- 240', wood plug, rock bridge and 20 sacks cement.
240- 30', mud.
30' to base of cellar, wood plug and 10 sacks of cement.

11-6-56
RECEIVED
STATE CORPORATION COMMISSION
NOV - 6 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wilson, Inc. - Chas. D. Wilson, Operator
Address 2921 Bonita, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of Nov November, 19 56

My commission expires March 12, 1959. H. E. Smith Notary Public.

PLUGGING
FILE SEC 7 T. 27 R. 12W
BOOK PAGE 102 LINE 31

WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Deistler
 Location 825' North and 990' West of E/4 Corner Sec. 7 T. 27 R. 12W
 Elevation 1883 (1881 Gr.) County Pratt State Kansas
 Drlg. Comm. October 3, 1950 Contractor Holm Drilling Company
 Drlg. Comp. November 9, 1950 Acid 500 gals. 11-2-50 at 4271'
 T. D. 4290' Initial Prod. Swabbed and flowed oil, no water, 24 hrs. (11-15-50)
 P. D. 4287'

CASING RECORD:

8-5/8" @ 404' cas. 275 ex cement
 5-1/2" @ 4237' cas. 200 ex cement

FORMATION RECORD:

sand & clay	0-100
shale & shells	225
red bed	750
shale	900
anhydrite	925
shale	1730
lime, shells & shale	1885
lime & shale	2105
shale	2630
lime & shale	2800
shale & lime	2990
lime & shale	3215
shale & lime	3280
lime & shale	3330
lime	3345
lime & shale	3555
shale & lime	3655
lime & shale	3845
lime	4120
lime & chert	4152
lime, chert & shale	4215
lime	4241

4241 STD = 4238 BIN

sand 4289
 shale 4290 T. D.

Corr. Top Lansing	3705'
Corr. Top Mississippi	4120'
Corr. Top Simpson Shale	4211'
Corr. Top Simpson Dolomite	4233'
Top Simpson Sand	4239'
Penetration	51'
Total Depth	4290'

Loaded hole with 2500' water.

Show oil 4239-4266.
 Bailed 12 gals. oil per hr. for 13 hrs. at 4266.
 Deepened 4266-71; bailed 16 gals. oil per hr. for 7 hrs.

11-2-50 Acidized 500 gals., no increase in oil.
 Deepened 4271-80. 1560' oil in 6 hrs. 10 mins. at 4278-80. 1690' oil in 7 hrs. 5 mins. at 4280.

Swabbed 30' oil, no water, 15 hrs.
 11-9-50 Deepened 4280-90.

Shot 30 qts. 4252-62.

Cleaned out to 4287.

SYFO:	500'	00
	1000'	00
	1500'	00
	2000'	10
	2500'	10
	3000'	10
	3500'	10

SEP 26 1956

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 7 T. 27 R. 12W
 BOOK PAGE 102 LINE 31