

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-151-10209-0001
API NUMBER 15- Docket #E-8202

LEASE NAME ICHU

WELL NUMBER 19

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2970 Ft. from (S)N Line of Section (circle one)

3630 Ft. from (E)W Line of Section (circle one)

LEASE OPERATOR Iuka-Carmi Development LLC

SPOT LOCATION _____ - SW - SE - NW

ADDRESS P. O. Box 847

SEC. 7 TWP. 27 S. RGE 12 (E) or (W)

CITY, STATE, ZIP Pratt, KS 67124-0847

COUNTY Pratt

PHONE#(316) 672-2531 OPERATORS LICENSE NO. 31739

Date Well Completed _____

Charater of Well Input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 7-7-97

Date Plugging Completed 7-10-97

The plugging proposal was approved on 7-7-97 (date)

by Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? Plugged at State's request.

Producing Formation(s) _____ Depth to Top _____ Bottom _____ T.D. 4280 ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface	0	388 ft.	8 5/8	388 ft.	0
	Casing	0	4280 ft.	5 1/2	4280 ft.	0

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

5 1/2" at 4221' x/125 sx cement, 4 1/2 liner from 4218-4280' w/75 sx cement, PBTD 3760' Simpson perfs at 4248-53, 4229-37, 4218-21', Casing leaks at 2100, 1370, 411-460' Sand fill up at 3868'. 1st plug at 3730' with 50 sx cement, 2nd plug at 2100' with 30 sx cement, 3rd plug at 1370' with 50 sx cement, 4th plug at 460-0'. Full description on reverse side.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc.

License No. 5893

Address P.O. Box 847, Pratt, KS 67124-0847

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Golden Exploration

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) C/O Pratt Well Service Inc. Box 847 Pratt, Ks. 67124



Subscribed and sworn to before me this 25th day of August, 1997

Dorothy M. Furgason Notary Public

My Commission Expires: Feb. 6, 2001

8-2-97
RECORDED
INDEXED
11:33

Plugging report cont. on the ICHU 19

1st plug spotted 25sx common cement through tubing inside of 5 1/2" casing from 3868-3643', 2nd plug spotted plugs inside of 5 1/2" casing through 2 7/8" tubing at 2100' with 30 sx cement, 3rd plug at 1370' with 50 sx cement

Let cement set. Tagged top of hard cement at 1046'. Ran into soft cement at 920'. 4th plug pumped down 5 1/2" casing with 170 sx cement through holes in 5 1/2" casing at 460'. Had returns throughout pumping of cement up casing/surface pipe annulus. Returns excellent topoor at times. Cement did not circulate.

7/8/97 Ran tubing in and tagged top of cement inside 5 1/2" casing at 172" from surface. 5 1/2" X 8 5/8" annulus is communicated.

7/8/97 Topped out 5 1/2" casing and 5 1/2" X 8 5/8" annulus with redi-mix.

USED COMMON CEMENT w/3% cc BY SUN CEMENTING % ACIDIZING.

NO CASING RECOVERY.