

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-009-05997-0000  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County, Sec. 1 Twp. 16S Rge. (E) 12W(W)

Location as "NE/CNW/SW" or footage from lines Approx. SW NW NE

Lease Owner O. A. Sutton

Lease Name Woydziak Well No. 1

Office Address 407 Insurance Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 26 1962

Application for plugging filed June 26 1962

Application for plugging approved June 26 1962

Plugging commenced June 26 1962

Plugging completed June 26 1962

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation Depth to top Bottom Total Depth of Well 3385 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	276	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole and filled with mud to 270' with 4 sacks hulls and 25 sacks cement. Top Plug @ 35' with 1/2 sack hulls and 10 sacks cement. Hole was plugged at 1:30 A.M., June 26, 1962

RECEIVED  
STATE CORPORATION COMMISSION

06-28-62 JUN 28 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. S. Sutton Drilling Company  
Address 313 Insurance Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
E. B. Krider (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. B. Krider

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1962

Tommie Chafin  
Tommie Chafin Notary Public.

My commission expires March 1, 1965

Woydziak #1 - O. A. Sutton  
SW NW NE Section 1-16S-12W  
Barton County, Kansas

RECEIVED  
STATE CORPORATIONS COMMISSION

JUN 27 1962

CONSERVATION DIVISION  
Topeka, Kansas

Date Commenced - June 19, 1962  
Date Completed - June 26, 1962  
Elevation - 1874' K.B.  
Casing - 276' of 8-5/8" with 175 w/ HA5 cement

DRILLERS LOG

276 - 335	Shale/Red Bed
335 - 800	Shale
800 - 850	Shale/Red Bed
850 - 1180	Shale/Shells
1180 - 1510	Lime/Shale
1510 - 1850	Shale/Shells
1850 - 1980	Shale/Shells
1980 - 2150	Shale/Lime
2150 - 2400	Lime/Shale
2400 - 2575	Shale/Lime
2575 - 2730	Shale/Lime
2730 - 2860	Lime/Shale
2860 - 2955	Lime/Shale
2955 - 3075	Lime
3075 - 3115	Lime
3115 - 3225	Lime
3225 - 3310	Lime/Shale
3310 - 3339	Shale/Lime
3339 - 3340	Lime/Shale - D.S.T. #1
3340 - 3349	Arb - D.S.T. #2
3349 - 3354	Arb - D.S.T. #3
3354 - 3365	Arb
3365 - 3385	Arb
3385 -	Total Depth

STATE OF KANSAS )  
                          ) ss  
SEDGWICK COUNTY )

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON DRILLING COMPANY

By *J. S. Sutton*

Subscribed and sworn before me this 28th day of June, 1962

*Bevan J. Danner*

My Commission expires December 11, 1965