


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

15-009-20509-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 1 Twp. 16S Rge. (X) 12 (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE SW  
Lease Owner H-30, Inc., et al  
Lease Name Schauf "B" Well No. 10  
Office Address 200 North Main, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 1, 19 70  
Application for plugging filed Verbal Request 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced July 1, 19 70  
Plugging completed July 1, 19 70  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 3,365 feet (rotary total depth) to 550 feet. Set bottom plug at 550 feet and cemented with 50 sacks cement. Filled hole with heavy rotary mud to 280 feet. Set plug at 280 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cement to cellar with 10 sacks cement, 2 sacks cement in rathole. Cementing service performed by Sun Oilwell Cementing Company pump truck.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1970

CONSERVATION DIVISION  
Wichita, Kansas

7-6-70

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor H-30, Inc.  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Sedgwick, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art B. Rorer


200 North Main, Wichita, Kansas

(Address)

Subscribed and sworn to before me this 2nd day of July, 19 70

January 23, 1972

Joanne J. Steinman  
Joanne J. Steinman Notary Public.



KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H-30, Inc., et al

SEC. 1 T. 16S R. 12W  
LOC. C NW SE SW

FARM Schauf "B"

NO. 10

TOTAL DEPTH 3,365'  
COMM. June 24, 1970

COMP. July 1, 1970

COUNTY Barton

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

CASING

20  
15  
12  
13

10  
8-5/8"  
6  
5

290' cemented w/160 sx cement

ELEVATION 1881KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

		SAMPLE TOPS	
Post Rock & Clay	100	Anhydrite Top	734 + 1147
Shale	291	Anhydrite Base	764 + 1117
Shale & Sand	525	Topeka	2645 - 764
Shale & Red Beds	734	Queen Hill	2842 - 961
Anhydrite	764	Heebner	2929 - 1048
Shale	1530	Toronto	2950 - 1069
Lime & Shale	2315	Douglas	2962 - 1081
Shale & Lime	2482	Brown Lime	3022 - 1141
Shale w/ Lime Streaks	2656	Lansing	3035 - 1154
Shale & Lime	2887	Conglomerats	3314 - 1433
Lime	2930	Arbuckle	3347 - 1466
Shale & Lime	3017	Rotary T. D.	3365 - 1484
Lime & Shale	3071		
Lime	3315		
Shale, Lime & Chert	3348		
Lime	3365		
Rotary Total Depth	3365		

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer  
Arlo B. Romer

STATE OF KANSAS

COUNTY OF SEDGWICK

SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 2nd. day of July, 1970.

Joanne J. Steinman  
Joanne J. Steinman-Notary Public

My Commission Expires:

January 23, 1972

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas