

15009 - 05996 - 8800  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

BARTON County. Sec. 1 Twp. 16 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner PETROLEUM, INC.

Lease Name WOYDZIAK Well No. 1

Office Address ROUTE #2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 8-2- 19 64

Application for plugging filed 8-2- 19 64

Application for plugging approved 8-2- 19 64

Plugging commenced 8-2- 19 64

Plugging completed 8-2- 19 64

Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production - 19 -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2995 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	361'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDERED UP WITH HEAVY MUD TO 350', FOLLOWED BY 1/4 SACK HULLS, A WOODEN PLUG AND 25 SACKS CEMENT. MUDDERED UP WITH HEAVY MUD TO 40', FOLLOWED BY 1/4 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1964 08-24764

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY

Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

MONTE CHADD (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) [Signature]

ROUTE #2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of AUGUST, 19 64

My commission expires SEPTEMBER 23, 1967

[Signature]  
Notary Public.

# WELL LOG

COMPANY Petroleum, Inc

SEC. 1 T. 16S R. 12W

FARM Woydziak

NO. 1

LOC. App. NE SE NE


TOTAL DEPTH 2995'

COUNTY Barton

COMM. 7-27-64

COMP. 8-2-64

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 361' w/200 sx

ELEVATION 1865' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

70' Post Rock  
 300' Shale  
 360' Red Bed  
 440' Fine Sand and Pyrite  
 480' Sand  
 757' Shale and Red Bed  
 790' Anhydrite  
 860' Shale and Shells  
 1070' Shale  
 1445' Shale and Shells  
 1470' Shale and Lime Streaks  
 1800' Lime and Shale  
 2075' Lime  
 2485' Shale and Lime  
 2653' Lime and Shale  
 2995' Lime  
 2995' RTD

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1964

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Barton } 53

I, Sam N. Stephens of Garvey Drilling Company  
upon oath state the above and foregoing is a true and correct copy of the log of the Woydziak #1 well.

Subscribed and sworn to before me this 6th day of August 1964

My Commission Expires: September 23rd, 1967

NOTARY PUBLIC