


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

15-009-15672-0000

T - 16 NORTH R - 12W



Locate well correctly on above
Section Plat

Barton

County. Sec. 1 Twp. 16 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines
Lease Owner Frank J. Black
Lease Name Schauf Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 1-15-52 19
Application for plugging filed 1-20-61 19
Application for plugging approved 1-23-61 19
Plugging commenced 1-27-61 19
Plugging completed 1-29-61 19
Reason for abandonment of well or producing formation Casing collapsed @ 1146'

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation Depth to top Bottom Total Depth of Well 3305 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	470'	none
				5 1/2"	3300'	1168'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pipe had collapsed and was into @ 1150'-
ran 2 tubs sand-pulled pipe-mudded to 350'-
set 10' rock bridge-dumped 20 sks cement-
mudded to 40'-set 10' rock bridge-dumped
10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1961 02-15-61

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box 572, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF MCPHERSON, ss.
Frank J. Black (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1961

My commission expires July 16, 1963

JERRY PELTZMAN

Notary Public.

COPY

R. 12W

KANSAS

Production. D.D. 1440 b.o. /
960 Bl

Tops:	
Heebner	2918
Toronto	2937
Brown lime	3009
Lansing-Kansas City	3024
Arb.	3300

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1961
CONSERVATION DIVISION
Wichita, Kansas

Formation Record

SCHAUF
Lease Chem-Schauf

Well No. 1 3

FROM	TO	Formation	REMARKS
0	235	Lime and Shale.	
235	335	Shale.	
335	700	Sand and Shale.	
700	730	Shale and Shells.	
730	745	Anhydrite.	
745	1500	Shale and Shells.	
1500	1785	Lime and Shale.	
1785	1930	Lime.	
1930	2060	Lime and Shale.	
2060	2405	Shale and Shells.	
2405	2655	Lime and Shale.	
2655	2910	Lime.	
2910	2945	Lime and Shale.	Tops: Heebner - 2918' Toronto - 2937'
2945	3005	Shale.	
3005	3305	Lime.	Tops: Brown Limestone - 3009' L.K.C. - 3024' Arbuckle - 3300'

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1977
CONSERVATION DIVISION
Wichita, Kansas