

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Form CP-4
15-009-19303-0800
WELL PLUGGING RECORD

NORTH

			#

Locate well correctly on above
Section Plat

Barton County, Sec. 1 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW/SW/NE
Lease Owner Herman George Kaiser
Lease Name Woydziak Well No. B-1
Office Address 909 Palace Bldg. Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced Mar. 2, 1965
Plugging completed Mar. 4, 1965
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 1-21 1965
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ##### Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3323 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260'	None
				5 1/2	3323 1/2	2460'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Plugged back with sand from 3025' to 2860'. Mixed and dumped 5 sx. of cement from 2860' to 2820' with dump bailer. Pulled casing.
Mudded hole to 270'. ##### Set 10' rock bridge from 270' to 260'.
Mixed and dumped 25 sx. of cement from 260' to 185'. Mudded hole from 185' to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1965 03-26-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ace Pipe Pulling Co.
Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Barton, ss.
Russell D. Hoberecht (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me-God.

(Signature) Russell D. Hoberecht
Box 304 Great Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of March, 1965
Shiley V. Mann
Notary Public.

My commission expires March 1, 1966


John

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Horton Geo. Kaiser, et al**
 FARM **Opdialak** NO. **2**

SEC. **1** T. **160** R. **120**
 LOC. **06** OF **08** BL.

TOTAL DEPTH **3,324**
 COMM. **5-5-64** COMP. **5-17-64**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED



CASING

20	10	
15	8 3/8	230' Jan 8/175 #2
12	6	
13	5 1/2	3,324' Oct 1/150 #2

ELEVATION **1370** OF
1374 LF
1377 NB
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	0
Foot Rock	0
Shale & Clay	0
Shale & Shells	88
Shale & Red Bed (Hard Sand)	749
Shale & Red Bed	750
Anhydrite	775
Lime, Shale & Red Bed	1000
Shale & Lime	1000
Lime & Shale	1701
Shale & Lime	2715
Lime & Shale	2800
Lime	2900
Lime & Shale	2935
Shale & Lime	3077
Lime & Shale	3155
Lime	3224
Rotary T. S.	3324

Sample Tests

Anhydrite Top	755	-1122
Anhydrite Base	775	-1100
Tronols	2644	- 707
Reebnos	2728	-1191
Toronto	2804	-1007
Douglas	2938	-1181
Lanning	3033	-1155
Conglomerate	3110	-1031
Arbuckle	3200	-1043
Rotary T. S.	3324	-1077

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 2 1965
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.
Garnet L. Boucher

STATE OF KANSAS)
) SS:
 BARTON COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 21st day of May, 1964.

Lorraine Hay
 Lorraine Hay, Notary Public

My Commission Expires:
 December 3, 1964.