

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-22,963-00-00

LEASE NAME LaVerne

WELL NUMBER 2-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 2 TWP. 16S RGE. 12W (E) or (W)

COUNTY Barton

LEASE OPERATOR Petroleum Property Services, Inc.

ADDRESS 155 N. Market, Suite 1010 Wichita, KS 67202-1824

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 31142

Date Well Completed

Character of Well Oil

Plugging Commenced 12-17-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-21-93

The plugging proposal was approved on (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3336'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	485'	none
				4 1/2	3333'	2133'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom @ 3289' & 4 sks cement. Shot @ 2133, pulled up to 1600'. Pumped 35 sks w/100# hulls @ 1600. Pulled to 800, pumped 75 sks w/100# hulls. Pulled to 350, pumped 45 sks & circulated to surface. Pulled rest of pipe & squeezed in 30 sks to cap off. 60/40 pos 10% gel Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Property Services, Inc.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 93

Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
JAN 03 1994
1-03-94
CONSERVATION DIVISION
Wichita, Kansas