


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-009-19157-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 2 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW NW NE
Lease Owner Sterling Drilling Co.
Lease Name Weber Well No. 1
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-20-61 19
Plugging completed 2-22-61 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	243'	None
				5-1/2"	3415'	2319'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3382', ran sand to 3370' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Mudded hole to 240', set 10' rock bridge to 230' and ran 25 sacks of cement. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE. MAR 2 1961 3-2-67

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Drilling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 1961

May 20, 1964 Milton J. Volin Notary Public.



STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- WEBER #1
Located: C SW/4 NW/4 NE/4, Section 2-16S-12W, Barton Co., Kansas

OWNER: Sterling Drilling Company, Forchild Interests, Sooner Oil Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 12-26-59
COMPLETED: 1-6-60

ROTARY TOTAL DEPTH: 3415'

Log

CASING RECORD

0	-	245	Shale & Shells	
245	-	735	Shale	
735	-	760	Anhydrite	
760	-	1170	Red Bed	
1170	-	1260	Shale & Shells	
1260	-	1610	Shale & Lime	
1610	-	2080	Lime	
2080	-	2235	Shale & Lime	
2235	-	2465	Shale	
2465	-	2630	Shale & Lime	
2630	-	2675	Lime	
2675	-	2760	Shale & Lime	
2760	-	2940	Lime	
2940	-	3065	Lime & Shale	
3065	-	3340	Lime	
3340	-	3346	Arbuckle	
3346	-	3356	Lime, Arbuckle	
3356	-	3390	Lime & Chert	
3390	-	3415	Lime Arbuckle	T.D.

Set 8-5/8" surface casing @
243' with 165 sacks cement.

Set 5-1/2" casing @ 3414' with
100 sacks cement.

RECORDED
STATE COMMISSION

JAN 26 1961

CONSERVATION DIVISION
Wichita, Kansas