

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-21198-00-00  
Spot: NESESESW Sec/Twnshp/Rge: 14-16S-33W  
502 feet from S Section Line, 2397 feet from W Section Line  
Lease Name: CLEMENT Well #: 1-14  
County: SCOTT Total Vertical Depth: 4799 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256		WITH 180 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2017 4:45 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Revd. from: SID DEUTSCHER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1620' WITH 80 SX CMT. 3RD PLUG AT 810' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 04/16/2017 6:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1620' WITH 80 SX CMT. 3RD PLUG AT 810' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

INVOICED  
APR 28 2017

Remarks: USED 60/40 POZMIX 4% GEL, 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
APR 18 2017  
KCC DODGE CITY