

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-30249-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 25-20S-21W
2087 feet from S Section Line, 4561 feet from E Section Line
Lease Name: WELLS WILLIAM Well #: 1
County: NESS Total Vertical Depth: 4372 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3400		WITH 2 SX CMT
PROD	4.5	4365	0	WITH 250 SX CMT
SURF	8.625	250		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2017 8:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: KENT STRUBE Company: HARTMAN OIL Phone: (620) 786-4161

Proposed Plugging Method: SET CIBP @ 4300' WITH 2 SX CMT. TEST CASING. PERFORATE AT 1500' & SPOT 50 SX CMT WITH 25# HULLS. IF CASING DOESN'T HOLD PRESSURE SET CIBP @ 850'. PERFORATE AT 650' & PUMP 80 SX CMT OVER CASING VOLUME. 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2017 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3400' WITH 2 SX CMT. COULDN'T GET BELOW 3450' WITH PLUG. TESTED CASING TO 500# & HELD. PERFORATED AT 1500' & PUMPED 25 SX CMT WITH 100# HULLS, 25 SX CMT WITHOUT HULLS. PULLED TBG & PERFORATED AT 650' THEN PUMPED 80 SX CMT, THEN 40 SX CMT WITH 100# HULLS. MAXIMUM PRESSURE WAS 150#. TIED ONTO BACKSIDE & PUMPED 60 SX CMT. PRESSURED TO 300# & HELD. PULLED SWEDGE & TOPPED OFF WITH 60 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4365	4387	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

SK

RECEIVED
APR 11 2017
KCC DODGE CITY

INVOICED

Form CP-2/3

APR 28 2017