

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-01101-00-02
Spot: NESENWSW Sec/Twship/Rge: 5-35S-12W
1752 feet from S Section Line, 4286 feet from E Section Line
Lease Name: SCHOOL TRUST Well #: 1-5
County: BARBER Total Vertical Depth: 4857 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4740		WITH 2 X CMT
COND	13.375	119		WITH 100 SX CMT
PROD	5.5	4857	1900	WITH 250 SX CMT
SURF	8.625	282		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2017 2:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4740' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2017 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4740' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4833	4850		
4773	4785		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

RECEIVED
APR 13 2017
KCC DODGE CITY

Signed

Stephen J. Pfeifer
51A

INVOICED
(TECHNICIAN)

APR 28 2017