

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21309-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 5-35S-12W
4252 feet from S Section Line, 1971 feet from E Section Line
Lease Name: SCHOOL TRUST Well #: 18-5
County: BARBER Total Vertical Depth: 4960 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4775		WITH 2 SX CMT
PROD	5.5	4949	2000	WITH 350 SX CMT
SURF	8.625	456		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2017 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L LOEB Phone: (620) 886-2419

Proposed Plugging Method: SET CIBP @ 4775' & 2 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2017 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4775' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 740' WITH 50 SX CMT. 2ND PLUG AT 490' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4837	4839		
4822	4834		
4812	4816		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed Stephen J. P. Jensen
(TECHNICIAN)

RECEIVED
APR 13 2017
KCC DODGE CITY

SA

INVOICED
APR 28 2017