

To: 1-120386

API NUMBER 15-185-22,628 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S E I N E S E, SEC. 1, T 22 S, R 13

TECHNICIAN'S PLUGGING REPORT

Operator License # 62170
Operator: Globe Exploration, Inc.
Name & Address: 1311 Stone
Great Bend, Kans 67530

_____ feet from S section line
_____ feet from E section line

Lease Name Drach Well # 1
County Sto Pford 119.28
Well Total Depth 3670 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address Box 768 Great Bend Kansas 67530

Company to plug at: Hour: 9:00 AM Day: 18 Month: 3 Year: 19 90

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" casing @ 3670' cemented @ 12.5 sx Cem. Perforated @ 3636'-3640'
1st plug sand 5 1/2" casing back to 3586' & 5sx cement @ Dump Bailer
2nd plug Pump 4sx Hulls, 10sx gel, 50sx cement, 10sx gel, 1sx Hulls
release 8 5/8" plug and pump 100sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:00 AM Day: 18 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sand 5 1/2" casing back to 3636' & 4sx cement @
dump bailer

2nd plug pumped 4sx hulls, 10sx gel, 50sx Cement, 10sx gel
1sx Hulls, released 8 5/8" plug & pumped 100sx cement
Pumping Pressure 0-500# Shut in pressure 100#
Recovered 3049' of 5 1/2" casing

Remarks: Cemented by Allied Cementing 60-40 Poz-6 to gel
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-28-90

INV. NO. 27742

Signed Duane Rankin
(TECHNICIAN)