

8-2-88 15.185.22366-0000

1 120120

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 3/28/86

NW NW SE, SEC. 1, T 22 S, R 13 W/E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9388

Lease Name Drach Well # 1

Operator: Mark E. Dobrinski
Name &

County Stafford 121.06

Address Box 147

Well Total Depth 3725 feet

Lorraine, KS 67459

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 2 Month: 8 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3724' Perfs at 3454-3708' (6 sets)

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION 8-4-88

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

AUG - 4 1988

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed Hour: 10 a.m. Day: 2 Month: 8 Year: 19 88
Wichita, Kansas

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2041' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (I should observe this plugging.)

Signed Duane Rankin
(TECHNICIAN)

DATE 8-11-88

INV. NO. 21835