

1 050834

15-185.30009.0000

111 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled in 10-29-64  
NE NW NW, SEC. 9, T 22 S, R 11

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Fair Well # 1

Operator: Rains & Williamson Oil Co., Inc.  
Name & Address 435 Page Court  
220 W. Douglas  
Wichita, KS 67202

County Stafford 112.42

Well Total Depth 3459 Simpson feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 228

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Ellis County Drilling License Number 6923

Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 9:50 am Day: 18 Month: July Year: 19 86

Plugging proposal received from Jack Davis

(company name) Rains & Williamson (phone) 316-265-9686

were: 5 1/2" at 3459' P.B.T.D. 3441' Perfs at 3297-3300'

1st plug sanded back to 3250' and dump 5 sx cement on top of sand through bailer

2nd plug pumped down 8 5/8" surface pipe with 3 sx hulls, 10 sx gel, 50 sx cement,

5 sx gel, 1 sack hulls, released 8 5/8 wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:45 am Day: 18 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3100' and dumped 5 sx cement on top

of sand through bailer, 2nd plug pumped down 8 5/8" surface pipe with 3 sx hulls,

10 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, released 8 5/8" wiper plug and

pumped 100 sx cement.

RECEIVED  
CORPORATION COMMISSION  
WICHITA, KS

7-21-86

JUL 21 1986

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Recovered 11744' of 5 1/2" casing. Used 60/40 Poz '6% gel by B. J. Titan

(If additional description is necessary, use BACK of this form.)

could observe this plugging.

INVOICED  
JUL 23 1986

Signed Richard W. Lacey  
(TECHNICIAN)

DATE

14431

INV. NO.

7-18