

To: 1 08008
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15.055.10092-0000

API NUMBER 15- Spud date 5/10/61

SW SW NW, SEC. 16, T 22 S, R 33 W/8
2970 feet from S section line
4950 feet from E section line

11-20

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427
Operator: D.R. Lauck Oil Company, Inc.
Name & Address: 221 S. Broadway, Ste. 400
Wichita, KS 67202

Lease Name Euwer B Well #/ 2
County Finney 154.05
Well Total Depth 4740 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 240

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 20 Month: 11 Year: 19 96

Plugging proposal received from James Ray
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Remarks: 7" at 4739' w/1200 gallons Latex, BP at 4400', Perfs at 4682-94, 4422-32' 11-27-96
1st plug CIBP set at 4400' with 7 sx cement on top,
2nd plug at 3000' with 100 sx cement, 3rd plug at 1150' with 100 sx cement,
4th plug at 600' with 75 sx cement, 5th plug at 260' with 75 sx cement,
5th plug at 40' with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 20 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug CIBP set at 4400' with 7 sx cement on top,
11/19/96 - Log Tech perforated at 3000' and 1150'.

2nd plug ran 2 3/8" tubing to 3000' and spotted 100 sx cement, pulled out, ran 7" packer to
1109', squeezed with 100 sx cement. 800 psi maximum pressure. Shut in pressure 300 psi.
3rd plug shot 7" at 620', pumped 75 sx cement,
4th plug pulled to 260' and pumped 75 sx cement, 5th plug pulled to 40' and pumped 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Allied. Recovered 620' of 7" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 03 1996
INV. NO. 47085

Signed *Kevin P. Shabo*
(TECHNICIAN)