

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10195-00-00
Spot: CSWNWSW Sec/Twnshp/Rge: 7-27S-12W
1650 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: ICHU Well Number: 26
County: PRATT Total Vertical Depth: 4308 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

Conductor Pipe: Size feet: 8 1/4
Surface Casing: Size 8.625 feet: 392 WITH 150 SX CMT
Production: Size 5.5 feet: 4247 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/18/2002 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GERALD INSLEE Company: IUKA-CARMI DEVELOPMENT Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 4150' & 2 SX CMT. CIBP @ 2655'. PERFORATE AT 700'. FILL 5 1/2" CASING WITH CMT. CIRCULATE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/18/2002 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4262'. OPEN HOLE 4247-4262'. SET CIBP @ 4150' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SET CIBP @ 2655' ABOVE CASING LEAK. PERFORATED 5 1/2" CASING AT 700'. PUMPED DOWN 5 1/2" CASING WITH 300 SX CMT. CMT DID CIRCULATE OUT 5 1/2" / 5/8" ANNULUS TOWARD TAIL END OF JOB.

RECEIVED
NOV 22 2002 11-22-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 11-22-02

INV. NO. 2003060858

Form SR-23