

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30093-00-00  
Spot: NENESE Sec/Twnshp/Rge: 17-34S-15E  
2330 feet from S Section Line, 285 feet from E Section Line  
Lease Name: MCCONNELL Well #: 2  
County: MONTGOMERY Total Vertical Depth: 1351 feet

Operator License No.: 32993  
Op Name: CALUMET-EAKIN GAS COMPANY, LL  
Address: 701 CEDAR LK BLVD  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1375		110 SX CMT.
SURF	8.625	211		75 SX CMT.

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: FRANK BELLAMY Company: \_\_\_\_\_ Phone: (918) 277-6201

Proposed Plugging Method: MIRU SERVICE UNIT. BLEED OFF ANY PRESURE, THEN TIE ON CEMENTING UNIT TO 4 1/2" CSG & DISPLACE WELL BORE W 120 SKS CLASS 'A' MIXED AT 14.7 PPG WITH A YEILD OF 1.36 CU-FT/SK. WOC THEN CUTOFF 8 5/8" & 4 1/2" CASING STRINGS 3' BELOW GL. CAP 8 5/8 W/STEEL PLATE INDICATING WELL NUMBER AND DATE PLUGGED. HAUL OFF EQUIPMENT AND REMOVE ANCHORS. THEN RESTORE LOCATION.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 10/01/2007 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

This well was plugged prior to my employment with the KCC. I contacted Chaperrel Energy LLC which is the company that aquired Calumet-Eaken Gas Company and they provided the following informaiton about the plugging of this well. Consolidated Oil Well Services hooked onto casing and pumped 120 sacks of cement down casing. Well was shut in with 550 psi on casing. Cement invoice #217022 attached. I gps'd well location and corrected accordingly.

Perfs:

Top	Bot.	Thru	Comments
1297	1299		RIVERTON
1036	1037		WEIR-PITTS.
899	900		BEVIER
889	890		IRON POST

RECEIVED  
KCC DIST #3  
APR 27 2017  
CHANUTE, KS

DS  
KCC WICHITA

MAY 01 2017

RECEIVED

Remarks:

Plugged through: CSG

District: 03

Signed

*Dual*

(TECHNICIAN)

5-1-17

FOR IMAGING ONLY - PLUG DATE EXCEEDS 5 YR BILLING CUTOFF

STILL OUTSTANDING

REC'D OCT 09 2007



**CONSOLIDATED  
OIL WELL  
SERVICES, LLC**

**REMIT TO**  
Consolidated Oil Well Services, LLC  
Dept. 970  
P.O. Box 4346  
Houston, TX 77210-4346

MAIN OFFICE  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE

Invoice # 217022

Invoice Date: 10/05/2007 Terms: 0/30,n/30

Page 1

CALUMET OIL COMPANY  
C/O CHAPARREL ENERGY LLC  
701 CEDAR LAKE BLVD  
OKLAHOMA CITY OK 73114  
(405)426-4499

MCCONNELL #2 AFE 06PA079  
12722 5522.001  
10-01-07 12/6 CP

AFE BEGIN DATE IS 12/20/07 PER MIKE PEARMAN.  
SERVICE DATE CHANGED TO ALLOW ENTRY.  
1/9/08 PJB

Part Number	Description	Qty	Unit Price	Total
11045	CLASS "A" CEMENT (SALE)	120.00	12.2000	1464.00
463	P & A OLD WELL	1.00	390.00	390.00
463	EQUIPMENT MILEAGE (ONE WAY)	.00	3.30	.00
479	MIN. BULK DELIVERY	1.00	285.00	285.00

**KCC WICHITA  
MAY 01 2017  
RECEIVED**

Parts:	1464.00	Freight:	.00	Tax:	77.59	AR	2216.59
Labor:	.00	Misc:	.00	Total:	2216.59		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_ Date \_\_\_\_\_

BARTLESVILLE, OX  
918/338-0808

ELDORADO, KS  
316/322-7022

EUREKA, KS  
620/563-7664

GILLETTE, WY  
307/686-4914

MCALISTER, OK  
918/426-7667

OTTAWA, KS  
785/242-4044

THAYER, KS  
620/839-5269

WORLDWIDE, WY  
307/347-4577

CONSOLIDATED OIL WELL SERVICES, *INC.*  
 P.O. BOX 884, CHANUTE, KS 66720  
 620-431-9210 OR 800-467-8676

*ENTERED*

TICKET NUMBER 12722  
 LOCATION FUGGUT  
 FOREMAN RICK LUMBO

TREATMENT REPORT & FIELD TICKET  
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-1-07	979	McCormick #2				MC
CUSTOMER <i>Calumet-Eastern Gas Co. LLC</i>			TRUCK #			
MAILING ADDRESS <i>701 Cedar Lake Blvd</i>			DRIVER <i>Kyle</i>		TRUCK #	
CITY <i>Oklahoma City</i>			DRIVER <i>Shannon</i>		TRUCK #	
STATE <i>OK</i>			DRIVER			
ZIP CODE <i>73114</i>			DRIVER			

JOB TYPE P.T.A HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 4 1/2"  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT 14.8" SLURRY VOL \_\_\_\_\_ WATER gal/ft 5.2" CEMENT LEFT IN CASING \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_ DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: *Safety meeting. Rig up to 4 1/2" casing. Pumped into @ 4 gpm @ 700 PSI. Mixed 120 sacks regular class "A" cement @ 14.8" slurry. Shut casing in @ 550 PSI. Job complete. Rig down.*

"Thank you"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
545A	1	PUMP CHARGE <i>2nd well</i>	30.00	30.00
546	1	MILEAGE	1	1
1105	120 Sks	class "A" cement	12.80	1536.00
547	5.64	Gas mileage bulk tax	n/c	22.00
			<i>SALES TAX</i>	<i>11.59</i>
			<i>ESTIMATED TOTAL</i>	<i>2016.59</i>

*211058*

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_

*2216.59*

KCC WICHITA  
 MAY 01 2017  
 RECEIVED