

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30086-00-00
Spot: SESENE Sec/Twnshp/Rge: 20-34S-15E
3064 feet from S Section Line, 285 feet from E Section Line
Lease Name: MCCONNELL-CALUMET Well #: 1
County: MONTGOMERY Total Vertical Depth: 1461 feet

Operator License No.: 32993
Op Name: CALUMET-EAKIN GAS COMPANY, LL
Address: 701 CEDAR LK BLVD
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1375		110 SX
SURF	8.625	239		70 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: FRANK BELLAMY Company: _____ Phone: (918) 227-6201

Proposed Plugging Method: MIRU SERVICE UNIT. BLEED OFF ANY PRESURE, THEN TIE ON CEMENTING UNIT TO 4 1/2" CSG & DISPLACE WELL BORE W 120 SKS CLASS 'A' MIXED AT 14.7 PPG WITH A YEILD OF 1.36 CU-FT/SK. WOC THEN CUTOFF 8 5/8" & 4 1/2" CASING STRINGS 3' BELOW GL. CAP 8 5/8 W/STEEL PLATE INDICATING WELL NUMBER AND DATE PLUGGED. HAUL OFF EQUIPMENT AND REMOVE ANCHORS. THEN RESTORE LOCATION.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 10/01/2007 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

This well was plugged prior to my employment with the KCC. I contacted Chaperrel Energy LLC which is the company that aquired Calumet-Eaken Gas Company and they provided the following informaiton about the plugging of this well. Consolidated Oil Well Services hooked onto casing and pumped 120 sacks of cement down casing. Well was shut in with 400 psi on casing. Well cut off and location restored. Cement invoice #217021 attached. I gps'd well location I found below ground and corrected accordingly.

Perfs:

Top	Bot	Thru	Comments
1297	1299		
1064	1066		
925	926		
912	914		

KCC WICHITA
MAY 01 2017
RECEIVED

RECEIVED **5-1-17**
KCC DIST #3
APR 27 2017
CHANUTE, KS

DS

Remarks: WELL PLUGGED PRIOR TO MY EMPLOYMENT WITH THE KCC>

Plugged through: CSG

District: 03

Signed _____

Donald Sims

(TECHNICIAN)

STILL OUTSTANDING

REC'D OCT 09 2007



REMIT TO
 Consolidated Oil Well Services, LLC
 Dept. 970
 P.O. Box 4346
 Houston, TX 77210-4346

MAIN OFFICE
 P.O. Box 884
 Chanute, KS 66720
 620/431-9210 • 1-800/467-8676
 FAX 620/431-0012

INVOICE

Invoice # 217021

Invoice Date: 10/05/2007 Terms: 0/30,n/30

Page 1

CALUMET OIL COMPANY
 C/O CHAPARREL ENERGY LLC
 701 CEDAR LAKE BLVD
 OKLAHOMA CITY OK 73114
 (405)426-4499

MCCONNELL #1
 12721
 10-01-07

AFE: 06PA078
 5521.001
 12/6 CP

AFE BEGIN DATE IS 12/20/07 PER MIKE PEARMAN
 SERVICE DATE CHANGED TO ALLOW ENTRY.
 1/9/08 PJB

Part Number	Description	Qty	Unit Price	Total
1104S	CLASS "A" CEMENT (SALE)	120.00	12.2000	1464.00
	Description	Hours	Unit Price	Total
463	P & A OLD WELL	1.00	550.00	550.00
463	EQUIPMENT MILEAGE (ONE WAY)	40.00	3.30	132.00
479	MIN. BULK DELIVERY	1.00	285.00	285.00

KCC WICHITA
MAY 01 2017
RECEIVED

Parts: 1464.00 Freight: .00 Tax: 77.59 AR 2508.59
 Labor: .00 Misc: .00 Total: 2508.59
 Sublt: .00 Supplies: .00 Change: .00

Signed _____ Date _____

BARTLESVILLE, OK 918/338-0806 EL DORADO, KS 315/322-7022 EUREKA, KS 620/583-7664 GILLETTE, WY 307/686-4914 McALESTER, OK 918/426-7667 OTTAWA, KS 785/242-4044 THAYER, KS 620/839-5269 WYOMING, WY 307/347-4577

