

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009 ²³⁴⁵⁶ ~~23,056~~ ~~0000~~
NE, Sec. 1, T 16 S, R 12 W/E
815 feet from N/S section line
830 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6456

Lease Name Woydziak Well # 1

Operator: Shelter Hydrocarbon Inc.
Name & Suite 500
Address 7171 17th Avenue SW
Alberta, Canada

County Barton

Well Total Depth 3425 feet 111.32

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 390

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kandrilco, Inc. License Number 5889

Address 555 N. Woodland, Wichita, Ks.

Company to plug at: Hour: _____ Day: 2 Month: March Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Jack Dunlap

(company name) Kandrico Inc. (phone) (316) 793-8033

were: Order 170 sks cement 50/50 pozmix 6% gel 3% cal.cl. 1 sks hulls, 1-8⁵/₈ plug,

1 sk flow seal. Heavy mud between all plugs. Pump cement down drill pipe.

Elvarion 1864 Anhydrite 754-72 Arbuckle 3325 Dakota 1700

Signed Dale F. Batthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 PM Day: 3 Month: March Year: 1984

ACTUAL PLUGGING REPORT Circulate @ 3325 for 40 minutes

1st plug 25 sks @ 3325

2nd plug 25 sks @ 760

3rd plug 100 sks @ 500 mixed with 1 sk flow seal

1 sk hulls, push plug to 40'

4th plug 10 sks @ 40.

10 sks in Rat Hole

Cementing by: Allied
Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1984

CONSERVATION DIVISION
Wichita, Kansas

3-12-84

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Dale F. Batthazor ✓
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 3-14-84

INV. NO. 0245