

4-071030

2-2

15-009-15670-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- 4-28-45

SE SW SE /4 SEC. 01, 16 S, 12 W
330 feet from S section line
1650 feet from E section line

Operator license# 6568

Lease Schauf T well # 1

Operator: Kaiser Francis Oil Co.

County Barton

Address: P. O. Box 21468
Tulsa, Ok. 74121-1468

Well total depth 3313 feet ^{107.67}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 290 feet

Aband. oil well x, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Klema Well Service License#

Address: Russell, Ks. Claflin, Ks.

Company to plug at: Hour: 1:00 AM Day: 2 Month: February Year: 93

Plugging proposal received from: John Glenn

Company: Kaiser Francis Oil Co. Phone: 316-564-3214

Were: 8 5/8" - 290 ft. s.p. cwc w/200 sks cement. 5 1/2" casing set
at 3303' w/150 sks cement. Perfs 2846 - 3088. Proposal 400 sks 65/35
poz 8% gel and 5 sks hulls. Pump in with pump truck. Spot and displace
all cement through tubing. Perforate 5 1/2" casing at 720' and 470'.
2. Run tubing to a minimum of 3100'. Load both 5 1/2" casing and 5 1/2"
x 8 5/8" annulus with cement. Shut in under pressure.

STATE CORPORATION COMMISSION

Plugging Proposal Received by: Marion J. Schmidt

FEB 16 1993
02-16-93

Plugging operations attended by agent? All[x], Part[], None[]

CONSERVATION DIVISION
Wichita, Kansas

Completed: Hour: 1:00PM, Day: 2, Month: February, Year: 93

Actual plugging report: Kaiser Francis ordered 400 sks 65/35 poz 8% gel
5 sks hulls. Pumped in with pump truck. Spotted and displaced all
cement with tubing. 1. Perforated 5 1/2" casing at 720' and 470'.
2. 2 3/8" tubing at 3140' w/15 sks cement followed w/135 sks cement w/
4 sks hulls added. 3. 2 3/8" tubing at 1200' w/100 sks cement. Cement
circulated out of 5 1/2" casing. 4. Squeezed 5 1/2" casing w/65 sks
cement. Cement circulated out of 5 1/2" x 8 5/8" annulus. Shut in
annulus. Then squeezed 5 1/2" casing with an additional 85 sks cement
and w/1 sk hulls. Cemented by Allied.

Remarks:

Condition of casing(in hole):GOOD BAD x Anhy.plug:YES x NO
Bottom plug(in place):YES x, CALC , NO Dakota plug:YES x, NO
Plugged through TUBING x, CASING . Elevation: GL

I did[x] / did not[] observe the plugging.

Marion J. Schmidt
Marion J. Schmidt
(agent)

DATE 2-17-93

INV. NO. 37372

Form CP-2/3

2-2 APR 02 1993

INVOICED