

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
KANSAS STATE CORPORATION COMMISSION
10-21-66
OCT 21 1966

CONSERVATION DIVISION
WICHITA, KANSAS

15-185-11413-00-01

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morris Garvin

Complete Address: 201 E. Third, St Johns, Kansas

Lease Name Norris Well No. # 1

Location NW SW SW Sec. 27 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 10:00AM Day 18th Month Oct. Year 1966

The Above well was plugged as follows:

258' of 8 5/8" surface pipe, cement circulated. 3936' of 5 1/2" long string.
No attempt was made to recover any pipe. Hole was squeezed with 10 sacks
of Gel-Mud and 75 sacks of cement, pumped through a 5 1/2" swage into the long
string. The top of the cement was now at 256' in the 5 1/2". 5 1/2" was shot off
at 256', the shot went off in cement, 40' of 5 1/2" long string was recovered
from the hole, this pipe was in very bad condition, ate up with salt water.

When this hole was squeezed with 75 sacks of cement the cement went in to
the 5 1/2", and out through the holes, circulating the cement up into the surface
pipe. Hole was bailed down to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

Dear Greider:

This report is the replugging of Morris Garvin's, Norris # 1. The original plugging turned out better than I thought it would.

The 5½" long string was so ate up with holes, that when the cement was pumped into the 5½", it circulated out in the hole and up in the surface pipe.

Yours Truly

Archie Elving

Archie Elving