

16 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1964
12-7-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Muir Thompson Inc. 15-185-19437-0000

Complete Address: 201 Garlinghouse Bldg., Topeka, Kansas

Lease Name Lutz "B" Well No. # 1

Location NE SW NE Sec. 27 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3950

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: M. S. T. Drilling Company Inc.

Address: 201 Garlinghouse Bldg., Topeka, Kansas License No.

Operation Completed: Hour 3:30PM Day 5th Month Dec. Year 1964

The Above well was plugged as follows:

287' of 8 5/8" surface pipe, cement circulated with 170 sacks. Fluid
level in the hole was at 50'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 275', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/7/64
INV. NO. 291-W

Signed: Archie Elving
Well Plugging Supervisor