

7
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-30282-0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority
issued December 15, 1966

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 23 1967
CONSERVATION DIVISION
WICHITA, KANSAS

1-23-67

Operator's Full Name Bulldog Pipe & Supply Company

Complete Address: 311 Mayo Bldg., Tulsa, Oklahoma

Lease Name Pauline Garner Well No. # 1

Location NE SE NW Sec. 27 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3957'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 10:45AM Day 21st Month Jan. Year 1967

The Above well was plugged as follows:

283' of 8 5/8" surface pipe, cemented with 275 sacks. 3956' of 5 1/2" long string, cemented with 125 sacks. Top perferation 3905'. Bottom of the hole was sanded to 3806', and cemented with 5 sacks, through the dump bailer.

3044' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'. 3 sacks of cement was mixed in a barrel, and put on plug at 250', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 22 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 1/23/67
INV. NO. 4647-U