

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-185-30064-0000

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1965
5-24-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Northeastern Petroleum Company

Complete Address: 2400 North Main St., Hutchinson, Kansas

Lease Name Davidson Well No. # 1

Location C S/2 SW SW Sec. 27 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3935'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Northeastern Petroleum Company

Address: 2400 N. Main St., Hutchinson, Kansas License No.

Operation Completed: Hour 4:00 AM Day 22nd Month May Year 1965

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cement circulated with 225 sacks. Bottom
joint of surface pipe had shook off, and went down the hole. Fluid
level in the hole was at 20'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 235', and cemented with 25 sacks, through the
drill pipe. Fluid level in the hole was now at 35', 2nd cementing
plug was bridged solid with dry cement and hulls on fluid at 35', and
cemented with 10 sacks to the base of the cellar. Rat hole was bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/24/65

INV. NO. 1204-W