

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1964

 6-3-64
 CONSERVATION DIVISION
 Wichita, Kansas

 J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas
Operator's Full Name Woody's Quality Oil CompanyComplete Address: 1119 Cravens Bldg., Oklahoma City, Oklahoma.Lease Name Soeken Well No. # 5Location N/2 SW NE Sec. 15 Twp. 22 Rge. 13 (E) (W)County Stafford Total Depth 3840Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Tommy Ward Drilling CompanyAddress: 609 Liberty Bank Bldg., Oklahoma City, Okla. License No. Operation Completed: Hour 8:30PM Day 1st Month June Year 1964

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cement circulated. Fluid level was up in
the hole. 1st cementing plug and 1/2 sack hulls was pushed to 280', in fluid,
and cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged solid with hulls, and
cemented with 10 sacks to base of the cellar.

Rat and mouse hole bridged and cemented with 4 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/3/64INV. NO. 9255-44
 Signed: Archie Elving
 Well Plugging Supervisor