

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued July 5, 1967

Operator's Full Name Sooner Pipe & Supply Corporation  
 Complete Address 301 Petroleum Club Bldg., Tulsa, Oklahoma 74119  
 Lease Name Soeken Well No. # B-3  
 Location SW SE NE Sec. 15 Twp. 22 Rge. 13 (E) (W) W  
 County Stafford Total Depth 3910'  
 Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
 Other well as hereafter indicated         
 Plugging Contractor Southwest Casing Pulling Company  
 Address Box 364, Great Bend, Kansas 67530 License No. 399  
 Operation Completed: Hour 2:45 P.M. Day 13th Month July Year 1967

The above well was plugged as follows:

270' of 8 5/8" surface pipe, cemented with 400 sacks. 3909' of 4 1/2" long  
string, cemented with 200 sacks. Plug back T.D. 3814'. No record of any  
perforations. Bottom of the hole was sanded to 3700', and cemented with 4  
sacks, through the dump bailer. 2915' of 4 1/2" long string was recovered from  
the hole. Bridge plug was pushed in fluid to 260', bridge plug and rock  
bridge from 260' to 250'. 1 sack of cement and 1 sack of Cal-Seal was mixed  
in a barrel, and put on plug at 250', through the dump bailer, and let set  
for 3 hours. Hole was bailed dry and hole was filled with 3 1/4 yards of ready-  
mix cement from 244' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

INVOICED

JUL 17 1967

7-17-67

Signed: Audie Elving  
Well Plugging Supervisor

DATE 7/17/67 CONSERVATION DIVISION  
 INV. NO. 5980-u Wichita, Kansas