

KANSAS

4 STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 5, 1967.

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1967
7-28-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Sooner Pipe & Supply Corporation
Complete Address 301 Petroleum Club Bldg., Tulsa, Oklahoma 74119
Lease Name Soeken Well No. # B-4
Location N/2 S/2 NE Sec. 15 Twp. 22 Rge. 13 (E) (W) W
County Stafford Total Depth 3875'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company
Address Box 364, Great Bend, Kansas 67530 License No. 399
Operation Completed: Hour 10:45 A.M. Day 27th Month July Year 1967

The above well was plugged as follows:

270' of 8 5/8" surface pipe, cemented with 300 sacks. 3873' of 4 1/2" long string, cemented with 100 sacks. No record of any perforations. Bottom of the hole was sanded to 3700', and cemented with 4 sacks, through the dump bailer, with cement from 3700' to 3650'. 3260' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'. 3 sacks of cement was mixed in a barrel, and put on plug at 250', through the dump bailer, and let set over-night.

Hole was bailed dry, and hole was filled with 3 3/4 yards of ready-mix from 240' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/28/67INV. NO. 6031-W