

KANSAS

Form CP-3
Rev. 6-9-67

10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 7, 1967.

7-24-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Sooner Pipe & Supply Corporation

Complete Address 301 Petroleum Club Bldg., Tulsa, Oklahoma 74119

Lease Name Soeken Well No. # B-2

Location SE SW NE Sec. 15 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 4006'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 9:15 A.M. Day 22nd Month July Year 1967

The above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 350 sacks. 3988' of 4 1/2" long string, cemented with 200 sacks. Plug back T.D. 3580'. No record of any perforations. Bottom of the hole was sanded to 3450', and cemented with 4 sacks, through the dump bailer, cement from 3450' to 3400'. 1910' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'. 3 sacks of cement was mixed in a barrel, and put on plug at 250', through the dump bailer, and let set over-night. Next day hole was bailed dry, and hole was filled with 3 1/2 yards of ready-mix cement from 240' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/24/67

INV. NO. 6020-u