

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Co. Inc.

Complete Address Box 169 Russel, Ks

Lease Name Howard B Well No. 2

Location 0 W/2 SE/SE Sec. 15 Twp. 22 Rge. 13 (E) (W)

County Stafford Total Depth 3804

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lynch Casing Pulling Co.

Address Rt 4 Great Bend, Ks License No. 457

Operation Completed: Hour 1:00 PM Day 21 Month 12 Year 1970

The above well was plugged as follows:
285 ft of 8 5/8 surface pipe cemented with 275 sacks. 3794 ft
5 1/2 long string cemented with 125 sacks. Top perf. 3516 ft. Sand back
to 3500 ft, 5 sacks cement with bailer. Pulled 3000 ft of 5 1/2. Pump
2 sacks hulls, 15 sacks gel & 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: D Russell Bikerstein
Well Plugging Supervisor

DATE 12/28/70

INV. NO. 3111-W