

74  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

7-5-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Management Inc

Complete Address Box 922 Great Bend, KS

Lease Name Fisher Well No. 1

Location G E/2 NW/NE Sec. 13 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3658

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Midway Drlg Inc

Address Box 921 Great Bend, KS License No. 620

Operation Completed: Hour 4:00 PM Day 2 Month 7 Year 1973

The above well was plugged as follows:

258 ft 8 5/8 surface cement circulated. 3656 ft 5 1/2 long string cemented  
with 50 sacks. Open hole. Sand to 3600 ft, 5 sacks cement with  
bailer. Pulled 2200 ft 5 1/2. Set 10 ft rock bridge at 250 ft.  
Fill hole with 4 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell B. Bunker  
Well Plugging Supervisor

DATE 7/6/73  
INV. NO. 1591-W