


## DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 107-17LOCATION NE-NE-NWSEC. 13 TWP. 22 RGE. 13WDry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease MettscherOperator Stanolind Oil & Gas Co Address Box 7, Collinswood Ks.Field \_\_\_\_\_ County StaffordTotal Depth 3671 Feet.Plugging Contractor West Supply Company Inc.Plugging Contractor's License No. 14Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 200' C.W.C. 6" O.D. casing  
set 3663' w/ 130 sv cem. Sanded hole to  
3650' dumped 5 sv Cem. shot off and  
pulled 6" casing. Filled hole with  
heavy mud to 225' set rock bridge  
and dumped 25 sv cem. mud to 25'  
rock bridge and 10 sv cem. to base of cellar

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 21 1955

CONSERVATION DIVISION  
Wichita, Kansas

Warren H. Garner  
District Conservation Agent

Date May 19, 1955

5-21-55

