

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 7, 1967.

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1967
8-1-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sooner Pipe & Supply, Inc.
 Complete Address 301 Petroleum Club Bldg., Tulsa, Oklahoma 74119
 Lease Name Soeken Well No. # B-1
 Location NW NE NE Sec. 15 Twp. 22 Rge. 13 (E) (W) W
 County Stafford Total Depth 3871'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Southwest Casing Pulling Company
 Address Box 364, Great Bend, Kansas 67530 License No. 399
 Operation Completed: Hour 2:00 P.M. Day July 31 Month Year 1967

The above well was plugged as follows:

295' of 8 5/8" surface pipe, cemented with 230 sacks. 3861' of 4 1/2" long string, cemented with 100 sacks. Plug back T.D. 3580'. No record of any perforations. Top of cement 3400'. Bottom of the hole was sanded to 3450', and cemented with 4 sacks, through the dump bailer, with cement from 3450' to 3400'. 2995' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 285', bridge plug and rock bridge from 285' to 275'. 3 sack of cement was mixed in a barrel, and put on plug at 275', through the dump bailer, and let set over-night. Next day hole was bailed dry, and hole was filled with 3 3/4 yards of ready-mix cement, with cement from 275' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audine Elving
Well Plugging Supervisor

DATE 8/1/67INV. NO. 6058-W