



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 3 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
7-3-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Brougher of Joe Brougher Oil Company has this  
date requested permission to plug the following described well:

Mr. Joe Brougher guarantees payment of the plugging fee.

Operator's full Name: Joe Brougher Oil Company

Complete Address: 5513 Apache, Great Bend, Kansas 67530

Lease Name: Harzman Well No. # 7

Location: W/2 W/2 SW Sec. 33 Twp. 16 Rge. 11 (E)(W) W

County: Barton Total Depth 3370 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Russ Sullivan was instructed to plug the well as follows:

8 5/8" csg. 333' Cwc.

Sanded hole back to 3300' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, & 100 sax

cement with Halliburton Cementing Company's pump truck, cementing

from 340' to base of cellar.

Very truly yours,

Don L. Lusk  
Conservation Division Agent