

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Executive Secretary
STATE CORPORATION COMMISSION

OCT 07 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM

10-7-82 (To be filed by Plugging Agent)

Dear Sir:

Mr. Ralph Bell of Rockhold Engineering, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Santa Fe Pipe & Supply, Inc.

Complete Address: P.O. Box 562, Great Bend, Mo. 67530

Lease Name: Harzman Well No. 3

Location: SE SW SE Sec. 33 Twp. 16 Rge. 11 (E) (W)

County: Barton Total Depth: 3358'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Bell was instructed to plug the well as follows:

10 3/4" - 310' S.P. c.c. w/ common cement, 7" set at 3356' w/ common cement.
2' of open hole. Ordered 215 sacks 50/50 pro mix - 4% Gel. - 3% Gel. U., 5 sacks
hulls, 15 sacks Gel. 810 3/4" plug. Pumped in 10 3/4" 25 sacks cement.
Pumped in 7", 4 sacks hulls, 50 sacks cement, 15 sacks Gel., 70 sacks cement,
1 sack hulls, released plug & followed w/ 70 sacks cement.

Maximum pressure 350 pounds

Very truly yours,

[Signature]
Conservation Division Agent