



15-079-30000-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

September 11, 1965

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pine Pulling Co. this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Aladdin Petroleum Corporation

Complete Address: 209 Petroleum Bldg., Wichita, Kansas

Lease Name: Franz Well No. 1

Location: C N/2 N/2 NW Sec. 30 Twp. 22 Rge. 3 (W) X

County Harvey Total Depth 3646 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

Push 5 1/2" plug to 3310'. Fill hole with sand to 3300' and

cement with 5 sacks. Fill hole with mud to 310'. Set rock

bridge from 310' to 300' and cement hole with 20 sacks.

Fill hole with mud to 40'. Set rock bridge from 40' to 30'

and cap hole with 10 sacks.

Very truly yours,

[Signature]  
Conservation Division Agent