

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-079-19162-0001

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

December 2, 1964

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1964

CONSERVATION DIVISION
Wichita, Kansas

12-8-64

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Drillers Production Company, Inc.

Complete Address: 1020 Union National Bldg., Wichita, Kansas

Lease Name: Franz Well No. 1

Location: C SE SW Sec. 30 Twp. 22 Rge. 3 (X) (W) X

County Harvey Total Depth 620' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push 5 1/2" plug to 490'. Fill hole with sand to 480' and cement
hole with 5 sacks. Fill hole with mud to 340'. Set rock
bridge from 340' to 330' and cement hole with 20 sacks.
Fill hole with mud to 40'. Set rock bridge from 40' to 30'
and cap hole with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent