

State of Kansas



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

FORM - CP-2
15-079-19162-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

JAN 9 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Dick Maede of Sterling Drilling Co. has this

date requested permission to plug the following described well:

Mr. Maede guarantees payment of the plugging fee.

Operator's full Name: Drillers Production Co., Inc.

Complete Address: 1020 Union Nat'l Bldg, Wichita, Kansas

Lease Name: Franz Well No. 1

Location: C SE SW Sec. 30 Twp. 22s Rge. 3 /(E)/(W)

County Harvey Total Depth 1979' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Maede was instructed to plug the well as follows:

Pump 150 sax cement in hole at 490', Fill hole w/ gravel back to 400'

Set a plug at 400', Fill hole w/ gravel back to 300'. Set an overnite

plug of 1/2 sak hulls a halco plug and 25 sax cement. Top of cement

was at 265' ran 20 sax cement from 265' back to 200'. Filled hole w/

mud. back to 35' set a 5' bridge and ran 8 sax cement.

Fill rat hole w/ mud and 2 sax cement.

Very truly yours,

William J. Jones
Conservation Division Agent