

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-185-30248-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1966

COPIES SENT BY [unclear]
[unclear]

3-31-66

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Gale Metz of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Metz guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Fair Well No. # 3

Location: NW NE NW Sec. 9 Twp. 22 Rge. 11 (E) (W) W

County Stafford Total Depth 3500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Metz was instructed to plug the well as follows:

255' of 8 5/8" surface pipe, cement circulated with 160 sacks.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
Archie Elving