



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wood of Texaco has this

date requested permission to plug the following described well:

Mr. Wood guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: Box 2420, Tulsa, Oklahoma 74102

Lease Name: E.P. Ward Well No. 5

Location: SW SW Sec. 16 Twp. 22 Rge. 33 ~~(E)~~ (W)

County: Finney Total Depth 4847' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wood was instructed to plug the well as follows:

8 5/8" to 457' circulated w/ cement. 4 1/2" to 4846' cement ed.

Top perforations 4734' Plug bottom w/ 20 sacks cement.

Top of cement. 4500' Mud 4500' to 2260'

Spot 25 sacks cement 2260' to 2180' Mud 2180' to 457'

Spot 35 sacks cement 457' to 357' Mud 357' to 45'

Plug, Halls & 15 sacks cement 45' to 0' Very truly yours,

Conservation Division Agent