



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 12-9-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Holbright of Texaco Inc. has this date requested permission to plug the following described well:

Mr. Holbright guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: E.P. Ward Well No. 2

Location: C NW SE Sec. 16 Twp. 22 Rge. 33 (E) (W)

County: Finney Total Depth 4860' Oil Well X

Gas Well Input Well GWD Well D & A X Lost Hole

Mr. Holbright was instructed to plug the well as follows:

8 5/8" to 405' circulated w/ cement. 4 1/2" to 4850' cemented.

Top perforations 4690' Plug bottom w/ sand & 4 sacks cement.

Top of cement 4640' Mud 4650'-375'

Rock Bridge & 30 sacks cement 375' to 275' Mud 275' to 40'

Rock bridge & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
 Conservation Division Agent