



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Holbright of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Holbright guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: E.P. Ward Well No. 3

Location: C NW SW Sec. 16 Twp. 22 Rge. 33 (E) (W)

County: Finney Total Depth 4850' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Holbright was instructed to plug the well as follows:

8 5/8" to 413' circulated w/ cement. 5 1/2" to 4850' cemented.

Top perforations 4712' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4650' Mud 4650' to 410'

Rock bridge & 30 sacks cement 410' to 310' Mud 310' to 40'

Rock bridge & 10 sacks cement 40' to 0',

Very truly yours,

Edgar J. Eves  
Conservation Division Agent