


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 2 Twp. 16S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW  
Lease Owner Glickman Oil Company  
Lease Name Weber Well No. 5  
Office Address P. O. Box 3104, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 7, 1964  
Application for plugging filed September 7, 19 64  
Application for plugging approved September 7, 19 64  
Plugging commenced September 7, 19 64  
Plugging completed September 7, 19 64  
Reason for abandonment of well or producing formation Non Commercial



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan, Russell, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3362 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249.70'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Started laying down drill pipe @ 2:00 P.M. Finish laying down drill pipe and plug hole. Fill hole to 250' - set plug and hulls and cemented through pipe w/25 sxs. Fill hole to 40' set plug and hulls and cemented w/10 sxs and 2" rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 18 1964

9-18-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glickman Oil Company  
Address P. O. Box 3104, Wichita, Kansas 67211

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Milton Glickman (owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Milton Glickman  
P. O. Box 3104, Wichita, Kansas 67211  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 64

My commission expires November 19, 1967

Lorella Schauf  
Lorella Schauf Notary Public.

GLICKMAN OIL COMPANY

P. O. Box 3108

Wichita, Kansas

DRILLERS WELL LOG

Company: Glickman Oil Company

Location: SW SE NW

2-16S-12W

Farm: Weber

Well No. 5

Barton County, Kansas

Commenced: August 31, 1964

Elevation: 1879 R.B.

Completed: September 7, 1964

Total Depth: 3362 RTD

Casing: 8-5/8" @ 256' w/140 sxs

Production: D & A

Geologist: Max S. Houston

Figures Indicate Bottom of Formations

256	Soil Shale and Sand		
360	Shale and Red		
460	Sand		
748	Shale and Shells		
769	Anhydrite		TOPS
1550	Shales and Shells		
1640	Shale and Lime	748	Cim. Anhydrite
1850	Lime and Shale	2671	Topeka
2045	Lime and Shale	2952	Heebner
2660	Shale and Lime	3044	Brown Lime
2880	Lime and Shale	3061	Lansing
2930	Lime	3256	Base Kansas City
3055	Lime and Shale	3333	Conglomerate
3123	Lime		
3339	Lime		
3362	Conglomerate		
3362	RTD		

RECEIVED  
STATE CORPORATION COMMISSION

SEP 18 1964

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Weber # 5

Milton Glickman  
Milton Glickman

Subscribed and sworn to before me this 10th day of September, 1964

Lorella Schauf  
Lorella Schauf Notary Public

My Commission Expires: November 19, 1967