


WELL PLUGGING RECORD

The All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 2 Twp 16S Rge. 12W (X) (W)
Location as "NE/CNW/SW" or footage from lines. SE NE SE
Lease Owner Herman George Kaiser, Oil Producer
Lease Name Schauf Well No. 3
Office Address 909 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-1-63 19
Application for plugging filed 3-1-63 19
Application for plugging approved 3-1-63 19
Plugging commenced 3-1-63 19
Plugging completed 3-1-63 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	328	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1963

Bottom plug @ 320' with 30 sacks cement
Top plug 40' with 10 sacks cement

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 63

My commission expires April 1, 1963
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Herman George Kaiser, oil producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SCHAUF #3
 LOCATION: SE NE SE Sec. 2-16S-12W
 BARTON COUNTY, KANSAS
 COMMENCED: 2-22-63
 COMPLETED: 3-1-63

0	20	Surface Soil
20	328	Surface Soil & Shale
328	744	Shale & Redbed
744	774	Anhydrite
774	1020	Shale, Redbed, Shells
1020	1400	Shale & Lime
1400	1531	Lime & Shale
1531	2565	Lime
2565	2745	Lime & Shale
2745	3370	Lime
	<u>3370</u>	<u>Rotary Total Depth - D. & A.</u>

Set 8 5/8" used surface casing @ 328' Cemented with 175 sacks Sunset.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schauf #3, located SE NE SE of Section 2, Township 16 South, Range 12 West, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Byron Johnson
 Byron Johnson

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 8th day of March, 1963.

Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1963

RECEIVED
 STATE CORPORATION COMMISSION

MAR 11 1963

CONSERVATION DEPARTMENT
 WICHITA, KANSAS