

15-009-03238-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 10/28/62

LEASE NAME LaVerne Weber

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 16 RGE. 12 (W)

COUNTY Barton

Date Well Completed 10/28/67

Plugging Commenced 2/6/91

Plugging Completed 2/6/91

RECEIVED
STATE CORPORATION COMMISSION

2-19-91
FEB 19 1991

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 125 N. Market #1075 Wichita, KS 67202

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/6/91 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? Log attached to plugging application

Producing Formation Topeka, LKC
Arbuckle Depth to Top 2900 Bottom 3354 T.D. 3354

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	Oil & Water	2900	20	8 5/8	269	NONE
LKC	" "	3074	3252	5 1/2	3343	NONE
Arbuckle	" "	3343	54			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf 3 holes @ 850, run tubing and plug 2900-3354 with 50 SX 60/40 poz, 8% gel spot 50 SX 60/40 poz 2850-2510, circulate 110 SX 60/40 poz from 1100' to surface, pull tubing and pump down 5 1/2 with 195 SX 60/40 poz to 200 PSI. Displace 55 SX 60/40 poz between 8 5/8 and 5 1/2 at 350 PSI.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 125 N. Market #1074 Wichita, KS 67202-1710

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market #1075 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1991



[Signature]
Notary Public

My Commission Expires: 8/1/93